



NOTES:

1. DETENTION PIPE AND ALL CONNECTIONS SHALL BE WATERTIGHT.
2. CLEANOUT REQUIRED FOR THE FIRST 50' PIPE LENGTH AND FOR EVERY 100' THEREAFTER.
3. ACCESS RISERS ARE REQUIRED AT EACH END FOR FIRST 100' AND FOR EVERY 100FT LENGTH THEREAFTER.
4. PIPE MATERIAL: REINFORCED CONCRETE (ASTM C76, MIN CLASS III)



City of Lake Oswego  
Engineering Division

Erica Rooney, P.E. City Engineer

DETENTION PIPE  
TYPICALLY CLOSED

SD9-03

EFFECTIVE DATE: SEPTEMBER 14, 2020 NOT TO SCALE

DRAWING NUMBER